



500 West Big Beaver
Troy, MI 48084
troymi.gov



CITY COUNCIL AGENDA ITEM

Date: April 7, 2025

To: Frank Nastasi, City Manager

From: Robert J. Bruner, Deputy City Manager
Robert C. Maleszyk, Chief Financial Officer
Kyle Vieth, Controller
Kurt Bovensiep, Public Works Director
G. Scott Finlay, City Engineer

Subject: Authorization for Grant Submittal – Local Bridge Program

History

In 2019, the federal government used the general fund to supplement highway infrastructure funding. Michigan received \$93.5 million of the \$2.5 billion, from the Highway Infrastructure Program. The Michigan Department of Transportation (MDOT) has established a Local Bridge Bundling Program, utilizing the local share of the Fiscal Year Highway Infrastructure Program (HIP) to improve critical bridges in Michigan.

This is an opportunity to fund some bridges that might not otherwise find funding. Over the last decade, local agencies have been able to maintain the percentage of bridges in good or fair condition. However, recently, conditions have started to decline, and local agencies have not been able to make a significant reduction in the number of bridges in serious or critical condition. At the current condition level, Michigan lags behind its neighboring Great Lakes States and the national average in the percentage of good or fair bridges. Without increased funding, statistical forecasts predict bridge conditions will continue to decline.

The City of Troy engages OHM Advisors, a current Engineering Consultant, to perform all of the City's annual bridge inspections. The Beach Road mill and overlay project in 2023 revealed significant top deck delamination, which was repaired as part of the project. The repairs are a temporary measure until funding can be secured to replace the beams and top deck

Attached is the application prepared by OHM Advisors and reviewed by City Staff for the pursuit of Local Bridge Funding.

Financial

The Local Bridge Program requires a 5% match from the submitting agency. Currently, there is no requirement to obligate the necessary funds. City Staff will include funding during the appropriate budget year. Based on the bridge cost estimate worksheet, the total cost is \$925,000, and the City's share would be \$46,250.



500 West Big Beaver
Troy, MI 48084
troymi.gov

CITY COUNCIL AGENDA ITEM

Recommendation

City Staff recommends authorization to submit a grant application through the Michigan Department of Transportation Local Bridge Program to pursue funding for the replacement of the beams and top deck, at an estimated cost of \$925,000. The City of Troy will be responsible for 5% of this amount, or \$46,250.

MICHIGAN DEPARTMENT OF TRANSPORTATION

STR 13611

BRIDGE SAFETY INSPECTION REPORT

Facility	Latitude / Longitude	MDOT Structure ID	Structure Condition
BEACH ROAD	42.581 / -83.1976	634679200079B01	Fair Condition(5)
Feature	Length / Width / Spans	Owner	
ROUGE RIVER	24 / 39.9 / 1	City: TROY(6792)	
Location	Built / Recon. / Paint / Ovly.	TSC	Operational Status
0.3 MI N OF WATTLES	1981 / / / 2012	Oakland(23)	A Open, no restriction(A)
Region / County	Material / Design	Last NBI Inspection	Scour Evaluation
Metro(7) / Oakland(63)	5 Prestressed Concrete / 05 Box Bm/Gird- Multiple	04/20/2023 / O85G	5 Stable w/in footing



NBI INSPECTION

O85G

Inspector Name	Agency / Company Name	Insp. Freq.	Insp. Date
Adam Rychwalski	Orchard, Hiltz & McCliment Inc	24	04/20/2023

GENERAL NOTES

2023 inspection assisted by Nick Aukerman.

Concrete Box Beam w/ Timber Railings retrofitted with Concrete Barrier on the east side with Sidewalk and guardrail along the west side. Road construction happening at time of 2023 inspection. HMA milled through bridge, approaches, and beyond.

Repairs made to top of beams during road construction project in spring 2023 while road was closed. Approximately 75% of the top flanges were repaired. repairs included chipping deteriorated concrete and re-casting the top flanges of the adjacent box beams. Roadway was repaved after beam repairs. Recommend applying for superstructure replacement at next call for projects.

DECK

	04/19	04/21	04/23	
1. Surface (SIA-58A)	6	6	6	Transverse crack at both the north and south abutments. Cracks partially sealed. Longitudinal crack at centerline at cold joint partially sealed with 2'x1' pothole at midspan filled with cold patch. Spider web cracking in northwest quadrant mostly unsealed. Some random cracking at isolated locations. HMA surface milled at time of 2023 inspection. Potholes appear to be from deck deterioration. See deck comments for more detail. (EDIT 8-31-23 - see general comments on repairs made after inspection, surface repaved after repairs) (04/23) Transverse crack at both the north and south abutments. Cracks partially sealed. Longitudinal crack at centerline at cold joint partially sealed with 2'x1' pothole at midspan filled with cold patch. Spider web cracking in northwest quadrant mostly unsealed. Some random cracking at isolated locations. (04/21) Transverse crack at both the north and south abutments. Cracks sealed. Longitudinal crack at centerline at cold joint partially sealed with 2'x1' pothole at midspan. Spider web cracking in northwest quadrant mostly unsealed (04/19)
2. Expansion Joints	N	N	N	(04/23) (04/21) (04/19)
3. Other Joints	N	N	N	(04/23) (04/21) (04/19)
4. Railings	7	7	6	Jersey barrier on east side with vertical cracks. Guardrail on west side with no issues. West concrete barrier posts cracking with exposed rebar on north end. (04/23) Jersey barrier on east side with vertical cracks. Guardrail on west side with no issues. (04/21) Jersey barrier on east side with vertical cracks. Guardrail on west side with no issues. (04/19)
5. Sidewalks or Curbs	7	7		Minor cracking. Some settling at ends in approaches. (04/23) Minor cracking. Some settling at ends in approaches creating potential trip hazard. (04/21) Minor cracking. Some settling at ends in approaches creating potential trip hazard. (04/19)
6. Deck Bottom Surface (SIA-58B)	N	N		Side-by-side box beams. See deck and stringer comments. (04/23) Side-by-side box beams. See deck and superstructure comments. (04/21) Side-by-side box beams. See deck and superstructure comments. (04/19)

MICHIGAN DEPARTMENT OF TRANSPORTATION

STR 13611

BRIDGE SAFETY INSPECTION REPORT

Facility	Latitude / Longitude	MDOT Structure ID	Structure Condition
BEACH ROAD	42.581 / -83.1976	634679200079B01	Fair Condition(5)
Feature	Length / Width / Spans	Owner	
ROUGE RIVER	24 / 39.9 / 1	City: TROY(6792)	
Location	Built / Recon. / Paint / Ovly.	TSC	Operational Status
0.3 MI N OF WATTLES	1981 / / / 2012	Oakland(23)	A Open, no restriction(A)
Region / County	Material / Design	Last NBI Inspection	Scour Evaluation
Metro(7) / Oakland(63)	5 Prestressed Concrete / 05 Box Bm/Gird- Multiple	04/20/2023 / O85G	5 Stable w/in footing



7. Deck (SIA-58)	6	6	5	<p>Surface in fair condition and stringers in fair condition. No deck on side-by-side box beams see surface and stringer comments. Large spalls in top of beams at midspan of west curbline and at north reference line. Rebar exposed in tops of beams 3 & 4 west. (EDIT 8-31-23 - see general comments on repairs made after inspection, surface repaved after repairs. Deck rating remains at fair due to beam condition at the time of inspection and construction) (04/23)</p> <p>Surface in fair condition and stringers in fair condition. No deck on side-by-side box beams see surface and superstructure comments. (04/21)</p> <p>Surface in fair condition and stringers in good condition. No deck on side-by-side box beams see surface and superstructure comments. (04/19)</p>
-----------------------------	---	---	---	---

8. Drainage	<p>Positive drainage present. Road crowns on bridge and slopes away on north and south side. Two catch basins along south approach. (04/23)</p> <p>Positive drainage present. Road crowns on bridge and slopes away on north and south side. Two catch basins along south approach. (04/21)</p> <p>Positive drainage present. Road crowns on bridge and slopes away on north and south side. Two catch basins along south approach. (04/19)</p>			
--------------------	---	--	--	--

SUPERSTRUCTURE

04/19 04/21 04/23

9. Stringer (SIA-59)	6	6	5	<p>13 adjacent box beams. Evidence of previous drainage from box weep holes and from between boxes. East fascia post tensioning duct grout pocket is spalled and has vegetation growing from it. Beam 7W has delamination 3/4 length along the north end 1' wide. Beam 5W middle half delaminated 1' wide. Beams 5W & 7W have 2 broken strands at delamination areas. Leaking with stalactites at most joints. For details on top of beams see deck comments. (EDIT 8-31-23 - see general comments on repairs made after inspection. No change to bottom flange condition) (04/23)</p> <p>13 adjacent box beams. Evidence of previous drainage from box weep holes and from between boxes. Fascia post tensioning duct grout pocket is spalled and has vegetation growing from it. Beam 7W has delamination 5' long by 1' wide at mid span of joint 6W and delamination at north end. Beam 5W middle third delaminated 1' wide. Leaking with stalactites at most joints (04/21)</p> <p>Evidence of previous drainage from box weep holes and from between boxes. North fascia post tensioning duct grout pocket is spalled and has vegetation growing from it. Beam 7W has delamination 5' long by 1' wide at mid span of joint 6W and delamination at north end. Beam 5W middle third delaminated 1' wide. Leaking with stalactites at most joints (04/19)</p>
10. Paint (SIA-59A)	N	N	N	<p>(04/23)</p> <p>(04/21)</p> <p>(04/19)</p>
11. Section Loss	N	N	N	<p>(04/23)</p> <p>(04/21)</p> <p>(04/19)</p>
12. Bearings	7	7	7	<p>Functioning as intended. Some debris and leaching (at curb lines) and staining. (04/23)</p> <p>Functioning as intended. Some debris and leaching (at curb lines) and staining. (04/21)</p> <p>Functioning as intended. Some debris and leaching (at curb lines) and staining. (04/19)</p>

SUBSTRUCTURE

04/19 04/21 04/23

13. Abutments (SIA-60)	7	7	7	<p>Some leaching stains from leakage from backwall. A few minor hairline cracks. Separate ~2" at all abutment/wingwall interfaces and no joint sealer in place. Tree growing between abutment and wingwall on SW quadrant trimmed but not removed. Cracking south abutment beam 7W bearing area. (04/23)</p> <p>Some leaching stains from leakage from backwall. A few minor hairline cracks. Separate ~2" at all abutment/wingwall interfaces and no joint sealer in place. Tree growing between abutment and wingwall on SW quadrant trimmed but not removed. (04/21)</p> <p>Some leaching stains from leakage from backwall. Area was dry at the time of inspections. A few minor hairline cracks. Separate ~2" at all abutment/wingwall interfaces and no joint sealer in place. Tree growing between abutment and wingwall on SW quadrant trimmed but not removed. (04/19)</p>
-----------------------------------	---	---	---	---

MICHIGAN DEPARTMENT OF TRANSPORTATION

STR 13611

BRIDGE SAFETY INSPECTION REPORT

Facility	Latitude / Longitude	MDOT Structure ID	Structure Condition
BEACH ROAD	42.581 / -83.1976	634679200079B01	Fair Condition(5)
Feature	Length / Width / Spans	Owner	
ROUGE RIVER	24 / 39.9 / 1	City: TROY(6792)	
Location	Built / Recon. / Paint / Ovly.	TSC	Operational Status
0.3 MI N OF WATTLES	1981 / / / 2012	Oakland(23)	A Open, no restriction(A)
Region / County	Material / Design	Last NBI Inspection	Scour Evaluation
Metro(7) / Oakland(63)	5 Prestressed Concrete / 05 Box Bm/Gird- Multiple	04/20/2023 / O85G	5 Stable w/in footing



14. Piers (SIA-60)	N	N	N	(04/23) (04/21) (04/19)
15. Slope Protection	N	N	N	(04/23) (04/21) (04/19)
16. Channel (SIA-61)	4	4	4	Channel meanders with several grass/mud islands on the east. Several fallen trees/branches on east side have dammed the direct flow through the channel and creating new paths for the water flow. Channel turns sharply south on west side of bridge. Poor alignment. (04/23) Channel meanders with several grass/mud islands on the east. Several fallen trees/branches on east side have dammed the direct flow through the channel and creating new paths for the water flow. Channel turns sharply south on west side of bridge. Poor alignment. (04/21) Channel meanders with several grass/mud islands on the east. Several fallen trees/branches on east side have dammed the direct flow through the channel and creating new paths for the water flow. Channel turns sharply south on west side of bridge. Poor alignment. (04/19)
17. Scour Inspection	5	5	5	Flow is deeper along south abutment down to riprap. Material buildup along north abutment. No scour noted noted but uneven channel. Steel sheet piling along north banks both east and west sides. Silted in riprap along south abutment (04/23) Flow is deeper along south abutment down to riprap. Material buildup along north abutment. No scour noted noted but uneven channel. Steel sheet piling along north banks both east and west sides. Silted in riprap along south abutment (04/21) Flow is deeper along south abutment down to riprap. Material buildup along north abutment. No scour noted noted but uneven channel. Steel sheet piling along north banks both east and west sides. Silted in riprap along south abutment (04/19)

APPROACH

	04/19	04/21	04/23	
18. Approach Pavement	7	7	7	HMA approaches milled at time of inspection. (04/23) HMA Approaches with hairline cracks. Most cracks are sealed. (04/21) HMA Approaches with hairline cracks. Most cracks are sealed (04/19)
19. Approach Shoulders Sidewalks	7	7	7	Sidewalk approach slabs have heaved on one side and settled on the other, creating a trip hazard. Sidewalk has a few cracks. HMA shoulders milled at time of inspection. (04/23) Sidewalk approach slabs have heaved on one side and settled on the other, creating a trip hazard. Sidewalk has a few cracks. HMA shoulders are in condition. (04/21) Sidewalk approach slabs have heaved on one side and settled on the other, creating a trip hazard. Sidewalk has a few cracks. HMA shoulders are in condition (04/19)
20. Approach Slopes				Steel sheet piling on north bank, but has heavy pack rust and some holes in the sheets. South bank is stable. (04/23) Steel sheet piling on north bank, but has heavy pack rust and some holes in the sheets. South bank is stable. (04/21) Steel sheet piling on north bank, but has heavy pack rust and some holes in the sheets. South bank is stable. (04/19)
21. Utilities				Two storm catch basins on south side approach. Utility poles/lines running north/south along west side and cross (east/west) just south of bridge. Water main running along east side of road. (04/23) Two storm catch basins on south side approach. Utility poles/lines running north/south along west side and cross (east/west) just south of bridge. Water main running along east side of road. (04/21) Two storm catch basins on south side approach. Utility poles/lines running north/south along west side and cross (east/west) just south of bridge. Water main running along east side of road. (04/19)

MICHIGAN DEPARTMENT OF TRANSPORTATION

STR 13611

BRIDGE SAFETY INSPECTION REPORT

Facility	Latitude / Longitude	MDOT Structure ID	Structure Condition
BEACH ROAD	42.581 / -83.1976	634679200079B01	Fair Condition(5)
Feature	Length / Width / Spans	Owner	
ROUGE RIVER	24 / 39.9 / 1	City: TROY(6792)	
Location	Built / Recon. / Paint / Ovly.	TSC	Operational Status
0.3 MI N OF WATTLES	1981 / / / 2012	Oakland(23)	A Open, no restriction(A)
Region / County	Material / Design	Last NBI Inspection	Scour Evaluation
Metro(7) / Oakland(63)	5 Prestressed Concrete / 05 Box Bm/Gird- Multiple	04/20/2023 / O85G	5 Stable w/in footing



22. Drainage Culverts

12" outlet pipe in SW wingwall w/ some sediment build up right at outlet. Invert at waterline.
 36" outlet pipe in NW wingwall w/ stones (debris on bottom of pipe). Invert approx. halfway below water line. Welded rebar screen on 36" outlet, steel is severely corroded (thin and broken off in some spots) at water line. (04/23)
 12" outlet pipe in SW wingwall w/ some sediment build up right at outlet. Invert at waterline.
 36" outlet pipe in NW wingwall w/ stones (debris on bottom of pipe). Invert approx. halfway below water line. Welded rebar screen on 36" outlet, steel is severely corroded (thin and broken off in some spots) at water line. (04/21)
 12" outlet pipe in SW wingwall w/ some sediment build up right at outlet. Invert at waterline.
 36" outlet pipe in NW wingwall w/ stones (debris on bottom of pipe). Invert approx. halfway below water line. Welded rebar screen on 36" outlet, steel is severely corroded (thin and broken off in some spots) at water line. (04/19)

MISCELLANEOUS

Guard Rail

<u>Item</u>	<u>Rating</u>
36A. Bridge Railings	1
36B. Transitions	1
36C. Approach Guardrail	1
36D. Approach Guardrail Ends	0

Other Items

<u>Item</u>	<u>Rating</u>
71. Water Adequacy	7
72. Approach Alignment	7
Temporary Support	0 No Temporary Supports
High Load Hit (M)	No
Special Insp. Equipment	2
Underwater Insp. Method	1

False Decking (Timber) Removed to Complete Inspection

N/A - No False Decking

Critical Feature Inspections (SIA-92)

	<u>Freq</u>	<u>Date</u>
92A. Fracture Critical		
92B. Underwater		
92C. Other Special		
92D. Fatigue Sensitive		

MICHIGAN DEPARTMENT OF TRANSPORTATION

STR 13611

STRUCTURE INVENTORY AND APPRAISAL

Facility	Latitude / Longitude	MDOT Structure ID	Structure Condition
BEACH ROAD	42.581 / -83.1976	634679200079B01	Fair Condition(5)
Feature	Length / Width / Spans	Owner	
ROUGE RIVER	24 / 39.9 / 1	City: TROY(6792)	
Location	Built / Recon. / Paint / Ovly.	TSC	Operational Status
0.3 MI N OF WATTLES	1981 / / / 2012	Oakland(23)	A Open, no restriction(A)
Region / County	Material / Design	Last NBI Inspection	Scour Evaluation
Metro(7) / Oakland(63)	5 Prestressed Concrete / 05 Box Bm/Gird- Multiple	04/20/2023 / O85G	5 Stable w/in footing



Bridge History, Type, Materials		Route Carried By Structure(ON Record)		Route Under Structure (UNDER Record)	
27 - Year Built	1981	5A - Record Type	1	5A - Record Type	
106 - Year Reconstructed		5B - Route Signing	5	5B - Route Signing	
202 - Year Painted		5C - Level of Service	1	5C - Level of Service	
203 - Year Overlay	2012	5D - Route Number	00000	5D - Route Number	
43 - Main Span Bridge Type	5 05	5E - Direction Suffix	0	5E - Direction Suffix	
44 - Appr Span Bridge Type		10L - Best 3m Unclr-Lt		10L - Best 3m Unclr-Lt	
77 - Steel Type	0	10R - Best 3m Unclr-Rt	99 99	10R - Best 3m Unclr-Rt	
78 - Paint Type	0	PR Number		PR Number	
79 - Rail Type	1	Control Section		Control Section	
80 - Post Type	1	11 - Mile Point	1.14	11 - Mile Point	
107 - Deck Type	2	12 - Base Highway Network	0	12 - Base Highway Network	
108A - Wearing Surface	6	13 - LRS Route-Subroute	0000006263 01	13 - LRS Route-Subroute	
108B - Membrane	2	19 - Detour Length	1	19 - Detour Length	
108C - Deck Protection	0	20 - Toll Facility	3	20 - Toll Facility	
Structure Dimensions		26 - Functional Class	19	26 - Functional Class	
34 - Skew	0	28A - Lanes On	2	28B - Lanes Under	
35 - Struct Flared	N	29 - ADT	3500	29 - ADT	
45 - Num Main Spans	1	30 - Year of ADT	1981	30 - Year of ADT	
46 - Num Apprs Spans	0	32 - Appr Roadway Width	24	42B - Service Type Under	5
48 - Max Span Length	22	32A/B - Ap Pvt Type/Width	5 24.02	47L - Left Horizontal Clear	
49 - Structure Length	24	42A - Service Type On	5	47R - Right Horizontal Clear	
50A - Width Left Curb/SW	4.8	47L - Left Horizontal Clear	0	54A - Left Feature	
50B - Width Right Curb/SW	7.8	47R - Right Horizontal Clear	24.0	54B - Left Underclearance	99 99
33 - Median	0	53 - Min Vert Clr Ov Deck	99 99	54C - Right Feature	
51 - Width Curb to Curb	24	100 - STRAHNET	0	54D - Right Clearance	99 99
52 - Width Out to Out	39.9	102 - Traffic Direct	2	Under Clearance Year	
112 - NBIS Length	Y	109 - Truck %	0	55A - Reference Feature	N
Inspection Data		110 - Truck Network	0	55B - Right Horiz Clearance	
90 - Inspection Date	04/20/2023	114 - Future ADT	4025	56 - Left Horiz Clearance	
91 - Inspection Freq	24	115 - Year Future ADT	2001	100 - STRAHNET	
92A - Frac Crit Req/Freq	N	Freeway	0	102 - Traffic Direct	
93A - Frac Crit Insp Date		Structure Appraisal		109 - Truck %	
92B - Und Water Req/Freq	N	36A - Bridge Railing	1	110 - Truck Network	
93B - Und Water Insp Date		36B - Rail Transition	1	114 - Future ADT	
92C - Oth Spec Insp Req/Freq	N	36C - Approach Rail	1	115 - Year Future ADT	
93C - Oth Spec Insp Date		36D - Rail Termination	0	Freeway	
92D - Fatigue Req/Freq	N	67 - Structure Evaluation	5	Proposed Improvements	
93D - Fatigue Insp Date		68 - Deck Geometry	2	75 - Type of Work	
176A - Und Water Insp Method	1	69 - Underclearance	N	76 - Length of Improvement	
58 - Deck Rating	5	71 - Waterway Adequacy	7	94 - Bridge Cost	
58A/B - Deck Surface/Bottom	6	72 - Approach Alignment	7	95 - Roadway Cost	
59 - Superstructure Rating	5	103 - Temporary Structure		96 - Total Cost	
59A - Paint Rating	N	113 - Scour Criticality	5	97 - Year of Cost Estimate	
60 - Substructure Rating	7	Miscellaneous		Load Rating and Posting	
61 - Channel Rating	4	37 - Historical Significance	5	31 - Design Load	6
62 - Culvert Rating	N	98A - Border Bridge State		41 - Open, Posted, Closed	A
Navigation Data		98B - Border Bridge %		63 - Fed Oper Rtg Method	6
38 - Navigation Control	0	101 - Parallel Structure	N	64F - Fed Oper Rtg Load	3.09
39 - Vertical Clearance	0	EPA ID		64MA - Mich Oper Rtg Method	6
40 - Horizontal Clearance	0	Stay in Place Forms		64MB - Mich Oper Rtg	3.04
111 - Pier Protection		143 - Pin & Hanger Code		64MC - Mich Oper Truck	18
116 - Lift Brdg Vert Clear	0	148 - No. of Pin & Hangers		65 - Inv Rtg Method	6
				66 - Inventory Load	1.85
				70 - Posting	5
				141 - Posted Loading	
				193 - Overload Class	

MICHIGAN DEPARTMENT OF TRANSPORTATION

STR 13611

WORK RECOMMENDATIONS

Facility	Latitude / Longitude	MDOT Structure ID	Structure Condition
BEACH ROAD	42.581 / -83.1976	634679200079B01	Fair Condition(5)
Feature	Length / Width / Spans	Owner	
ROUGE RIVER	24 / 39.9 / 1	City: TROY(6792)	
Location	Built / Recon. / Paint / Ovly.	TSC	Operational Status
0.3 MI N OF WATTLES	1981 / / / 2012	Oakland(23)	A Open, no restriction(A)
Region / County	Material / Design	Last NBI Inspection	Scour Evaluation
Metro(7) / Oakland(63)	5 Prestressed Concrete / 05 Box Bm/Gird- Multiple	04/20/2023 / O85G	5 Stable w/in footing



WORK RECOMMENDATIONS

O85G

Inspector Name	Agency / Company Name	Insp. Freq.	Insp. Date
Adam Rychwalski	Orchard, Hiltz & McCliment Inc	24	04/20/2023

RECOMMENDATIONS & ACTION ITEMS

Recommendation Type	Priority	Description
Super Repl.	M	Superstructure deteriorating. Replacement in the next few years recommended.

1a. Situation Map




Image taken from Google Earth

Beach Rd to Long Lake Rd
To N Adams Rd
To Wattles Rd
To Beach Rd

Detour: 3.0 miles (Note: Beach Rd is a NFC major collector and detour utilizes NFC major collector or greater road classifications.)

3. Photographs



Typical Approach



Typical Surface



Typical Elevation



Typical Abutment



Top Flange of Box Beam Deterioration



Top Flange of Box Beam Deterioration



Top Flange of Box Beam Deterioration



Top Flange of Box Beam Deterioration



Typical Leaching Joint Between Box Beams



Beam 5W Cracking



Beam 7W Delamination and Broken Strand

4. Application Requirements for Beach Rd over Rouge River

A. Local Agency Contact Person

Scott Finlay - City Engineer
City of Troy
500 W. Big Beaver Rd
Troy, MI 48084

B. The purpose of this application is for the rehabilitation of the bridge carrying Beach Road over Rouge River. Funding requested for a superstructure replacement, approach roadway and guardrail, and maintenance of traffic.

C. Economic Importance of the Structure

This structure is located in a residential area of Troy 0.33 miles north of Wattles Road. Beach Road Park is 0.33 miles north of the bridge.

Although there are no schools in the immediate area of the bridge, Beach Road is utilized by the school district for bussing purposes. If bus traffic is not able to cross the bridge it will put a financial burden on the already tight school budgets because of increased length of bus routes. Emergency vehicles would also be impacted by the closing as well, increasing response times. The bridge is also used by local residents to access Beach Road Park and the main roads of the area.

The structure is an adjacent prestressed concrete box beam structure with 1 24' span. The bridge is overall in fair condition and rated a 5. During a road rehabilitation in 2023 where the HMA surface was replaced, it was found that 75% of the top flanges of the beams had deteriorated and crumbled away. The unsound concrete was removed and recast. However, this is considered a temporary fix and only providing cover to the existing rebar in the beams. Additionally, beam 7W has a delamination $\frac{3}{4}$ of the length along the north end that is 1' wide. Beams 5W and 7W have 2 broken strands at delaminated areas. There is no structural deck, and the surface is newly paved HMA. The abutments are in good condition and rated a 7. There are small hairline cracks, cracking at south abutment beam 7W bearing area, some leaching stains, and a 2" gap between all abutment and wingwall interfaces with no joint sealer.

The recommended repair for the bridge is a superstructure replacement. The condition of the box beams warrants replacement due to the broken strands and deteriorated top flanges of the beams. Broken strands compromise the structural integrity and load carrying capacity of the beams. The deteriorated top flange of the beams has a temporary concrete patch with an unknown service life. The only way to repair the structure is to replace the beams. The substructure is in good condition, so a full replacement is not needed. The approaches should be replaced as well to provide a smooth transition to the

bridge deck from the approach. A smooth transition is important as it will prevent excess impact loads, which can result in damage to the superstructure of the bridge.

D. If there is a current detour, what does it affect?

Currently the bridge is open to traffic and there is no detour.

E. If the structure were to be closed, what would the detour affect?

If the structure were to be closed, the detour would affect the residents in the area. The school system, with its already tight budget, will have cost increases because of the need to reroute its buses and extend routes. Emergency vehicles would have to take a longer route to reach emergencies in the area. As seconds matters in an emergency, this could become a public safety issue. Access to Beach Road Park would be impacted as well by the closure of the bridge.

F. The structure is not currently closed.

G. Maintenance of the Structure

The HMA surface was replaced in 2023 as part of a road rehabilitation job. During the job, 75% of the top flanges of the box beams were found to have deteriorated. The deteriorated concrete was removed and the top flanges were recast.

5. Estimated Rehabilitation Costs

<u>Superstructure Replacement and Approach Work</u>	
A. Approach Construction	\$ 401,000.00
B. Structure Construction	\$ 524,000.00
Total (A & B)	\$ 925,000.00

For a breakdown of construction costs see Appendix A.

6. Priority List

1. Beach Rd over Rouge River

7. Resolution

The resolution is attached in Appendix B.

8. Previous Applications

It is understood that all previous applications have been discarded and that this application will be used to select funding.

APPENDIX A

Exhibit 4 - Cost Estimating Worksheet

2025

BRIDGE COST ESTIMATE WORKSHEET

REV. 02/6/2024

- CPM, REHAB, REPLACE -

OWNER:	TROY	FISCAL YEAR:		2028	Out to Out	Curb to Curb	ENGINEER:	AJR
REGION:	Metro				LENGTH	WIDTH		
TSC:	Oakland	PR: 626301	MP: 1.138		24.0	39.9	24.0	STRUCTURE ID:
								13611
	LOCATION:	BEACH ROAD over ROUGE RIVER						BRIDGE ID:
	PRIMARY WORK ACTIVITY	Superstructure Replacement			DECK AREA:	958	SFT	STR. TYPE:
	OTHER WORK:				CLEAR ROADWAY:	576	SFT	Box Beam or Girders - Mul

WORK ACTIVITY	MDOT Bridge Design Guides	QUANTITY	UNIT	UNIT COST	TOTAL
NEW BRIDGE (increase deck area based on design standards and hydraulic requirements)					
Single or Multiple Spans, Grade Separation	(add demo, approach, MOT)		SFT	\$435.00/SFT	
Single Span, Over Water	Length < 100ft (add demo, approach, MOT)		SFT	\$525.00/SFT	
Multiple Spans, Over Water	Length > 100ft (add demo, approach, MOT)		SFT	\$470.00/SFT	
Precast Culvert	Length < 40ft (add demo, approach, MOT)		SFT	\$565.00/SFT	
NEW SUPERSTRUCTURE					
New Superstructure, Grade Separation	(incl. remove exist deck/super; add MOT & approach)		SFT	\$310.00/SFT	
New Superstructure, Over Water	(incl. remove exist deck/super; add MOT & approach)	1,008.0	SFT	\$315.00/SFT	\$317,520.00
WIDENING					
Structure Widening, _____ ft	(incl. deck/super/sub widening, add approach transition)		SFT	\$630.00/SFT	
NEW DECK					
New Bridge Deck & Barrier	(incl. remove exist deck/railing, add approach, MOT)		SFT	\$150.00/SFT	
DEMOLITION					
Entire Structure, Grade Separation			SFT	\$75.00/SFT	
Entire Structure, Over Water			SFT	\$95.00/SFT	
DECK REPAIR / TREATMENTS					
Bridge Railing Replacement	(incl. removal and replacement)		FT	\$750.00/FT	
Concrete Brush Block / Curb Patch	(incl. hand chipping and formwork)		FT	\$29.00/FT	
Concrete Barrier Patch	(incl. hand chipping and formwork)		SFT	\$85.00/SFT	
Concrete Deck Patch	(incl. hand chipping)		SFT	\$68.00/SFT	
Deep Overlay	(incl. joint repl & hydro)		SFT	\$46.00/SFT	
Epoxy Overlay	(incl. warranty)		SYD	\$48.00/SYD	
Expansion Joint Gland Replacement	(remove and replace elastomeric gland)		FT	\$125.00/FT	
Expansion Joint Replacement	(incl. removal)		FT	\$860.00/FT	
Full Depth Patch			SFT	\$140.00/SFT	
Healer / Sealer	(penetrates cracks in bridge deck)		SYD	\$30.00/SYD	
HMA Overlay with WP membrane			SYD	\$60.00/SYD	
Overlay Removal	(Epoxy: \$22/syd Latex: \$26/syd HMA: \$7/syd)		SYD	\$22.00/SYD	
Reseal Bridge Joints			FT	\$28.00/FT	
Shallow Overlay	(incl. joint repl & hydro)		SFT	\$46.00/SFT	
SUPERSTRUCTURE REPAIR					
Bearing Realignment / Replacement	(incl. temporary supports)		EA	\$6,450.00/EA	
Heat Straightening	(incl. clean and coat)		EA	\$57,000.00/EA	
Pack Rust Repair	(greater than 3/8" separation)		FT	\$1,150.00/FT	
Paint - Complete	(incl. clean & coat)		SFT	\$30.00/SFT	
Paint - Partial / Spot / Zone	(incl. clean & coat - \$20k minimum)		SFT	\$60.00/SFT	
PCI Beam End Blockout	(incl. temporary supports)		EA	\$7,200.00/EA	
Pin & Hanger Replacement	(incl. temporary supports)		EA	\$17,000.00/EA	
Structural Steel Repair	(based on 6ft repair length)		EA	\$4,000.00/EA	
Structural Steel Repair - Stiffener	(includes each side of beam)		EA	\$1,500.00/EA	
SUBSTRUCTURE REPAIR					
Substructure Patching	(measured x 2) replace if repair area > 30%		CFT	\$360.00/CFT	
Substructure Replacement	(incl. temporary supports, excavation)		CFT	\$375.00/CFT	
Substructure Horizontal Surface Sealer			SYD	\$75.00/SYD	
Temporary Supports	(add Structural Steel Repair - Stiffener for ea steel beam)		EA	\$4,000.00/EA	
MISCELLANEOUS					
Articulating Concrete Block System (ACB)			SYD	\$320.00/SYD	
Concrete Surface Coating			SYD	\$47.00/SYD	
Culvert Cleanout			FT	\$125.00/FT	
Epoxy Crack Injection	(structural crack repair)		FT	\$70.00/FT	
Metal Mesh Panels	(48" width, max 6'-6" length)		SFT	\$28.00/SFT	
Pressure Relief Joint	(use when approach concrete roadway exceeds 1,000ft)		FT	\$110.00/FT	
Riprap	(assume 10ft distance around perimeter of substructure)	133.3	SYD	\$275.00/SYD	\$36,666.67
Silane Treatment	(penetrating sealer for concrete surfaces)		SFT	\$7.00/SFT	
Slope Protection Repairs			SYD	\$150.00/SYD	
Other					
STRUCTURE CONSTRUCTION BUDGET					\$354,187

ROAD WORK					
Approach Pavement, 12" RC	(incl. removal; add curb, gutter, guardrail) 40' ea. end	142.2	SYD	\$230.00/SYD	\$32,711.11
Approach Curb & Gutter	(incl. removal) 40' ea. quadrant	80.0	FT	\$57.00/FT	\$4,560.00
Guardrail Anchorage to Bridge	(each quadrant)	4.0	EA	\$2,540.00/EA	\$10,160.00
Guardrail	(incl. removal) < 200ft beyond reference line	100.0	FT	\$4.00/FT	\$4,100.00
Guardrail Terminal	(each quadrant)	4.0	EA	\$3,900.00/EA	\$15,600.00
Roadway Approach Work	(beyond approach pavement)	1.0	LSUM	\$150,000.00/LSUM	\$150,000.00
Utilities		1.0	LSUM	\$25,000.00/LSUM	\$25,000.00
TRAFFIC CONTROL Unit Cost to be determined by Region or TSC Traffic & Safety					
Part Width Construction			LSUM		LSUM
Crossovers			EA		/EA
Temporary Traffic Signals			set		/set
RR Flagging			LSUM		LSUM
Detour		1.0	LSUM	\$30,000.00/LSUM	\$30,000.00
RELATED ROAD/TRAFFIC CONSTRUCTION BUDGET					\$272,131

CONTINGENCY	(10% - 20%) (use higher contingency for small projects)	20	%	\$626,000.00	\$125,000
MOBILIZATION	(estimate at 10%)	10	%	\$751,000.00	\$75,000
INFLATION	(assume 4% per year, beginning in 2025)	12	%	\$826,000.00	\$99,000

(Does not include PE or CE)

TOTAL CONSTRUCTION BUDGET **\$925,000**

APPENDIX B

